## 

Sealed quotation is invited for initial pile load test from experienced registered agency for the following work in the campus of new police line, Patna as per IS:2911 (Part-IV):-

1. Pile 400mm dia 15m depth #12-8 rod/rings #8@6"C/C M25 & Fe500, Plain pile-2 Nos.

2. Pile 400mm dia 15m depth U/R dia -800mm # 12-8 Nos. rings #8@6"C/C-1 Nos.

Rates to be quoted complete with cost of all material and labour for pile work and testing work complete job. The last date for receipt of quotation in the office of chief engineer will be 22nd June 2018.

Loading on each pile will be 57T x 2.5=142.5T Security money in the form of bank draft of 5000/- payable to C.M.D., B.P.B.C.C. payable at Patna should be enclosed.

26/14 Chief Engineer Bihar Police Building Construction Corporation atna